

January 18, 2012

**TO:** All Bidders

**RE:** Hocking Valley Community Hospital  
Electrical Upgrades Building Addition  
Addendum No. 2

The following items listed below represent Addendum No. 2 and shall be incorporated into the Hocking Valley Community Hospital, Electrical Upgrades Building Addition construction documents.

1. **Generator Platform:** Provide access stairs and platform for Generator as follows:
  - Freestanding
  - Hand rails and guardrails
  - 10 gauge
  - Hot Dipped galvanized
  - 2" square tubing frame and rails
  - Open grate step treads and landing
  - 36" wide dimension
  - 36" x 72" platform
  - 4" concrete pad and reinforcing
  - Anchor steps to concrete with bolts
2. **Generator seismic rating:** Provide Seismic ratings on generator, switch gear, panel boards, and transfer switches
3. **Transfer switch:** LS transfer switch shall be 100 amp.

Very truly yours,

**TRINITY HEALTH GROUP**

**Ron Frissora, AIA**  
**Project Architect**